

DIAGNOSIS AND TESTING (Continued)

Condition	Source	Action
	● ICC	● Go to Section 413-08.
● Blower motor not operating on selected speed	● Can Message	● Refer to Section 412-04, Go to PinPoint Test M.
	● Blower Input Function	● Refer to Section 412-04, Go to PinPoint Test L.
● A/C not cold	● ICC	● Refer to Section 413-08.
	● Driver side Actuator Motor	● Go to PinPoint Test H.
	● Passenger side Actuator Motor	● Go to PinPoint Test G.
	● Low Refrigerant Charge	● Refer to Section 412-03.
	● A/C Compressor Not Engaging	● Refer to Section 412-03, Go to PinPoint Test A & B.
	● Evaporator Temperature Sensor	● Refer to Section 412-04, Go to PinPoint Test B.
	● Evaporator Core Ice-Up	● Go to section 412-03, Pinpoint test D.
	● Mode (HIM)	● Go to PinPoint Test D, E, F, G, H, J.
	● Ambient Air Sensor	● Refer to Section 412-04, Go to PinPoint Test A.
	● Cabin Temperature Sensor	● Refer to Section 412-04, Go to PinPoint Test P.
	● Blower Motor	● Refer to Section 412-04, Go to PinPoint Test L.
	● Passenger side temperature Hotter than Drivers side	● Go to PinPoint Test K.
	● Sun Load Sensor	● Refer to section 417-01.
● Heating ineffective	● Passenger side Actuator Motor	● Go to PinPoint Test G
	● Driver side Actuator Motor	● Go to PinPoint Test H.
	● Heater Core Issue/Engine cooling issue	● Go to PinPoint Test C.
	● Mode (HIM)	● Go to PinPoint Test D, E, F, G, H, J.
	● Ambient Air Sensor	● Refer to Section 412-04, Go to PinPoint Test A.
	● Cabin Temperature Sensor	● Refer to Section 412-04, Go to PinPoint Test P
	● ICC	● Refer to Section 413-08.
	● Leaking Heater Core	● Go to PinPoint Test C.
	● Blocked Heater Core/Engine Cooling system	● Go To section 303-03.
● Smell from HVAC through vents	● Leaking Evaporator Core	● Go to section 412-03, Pinpoint test E.
	● Evaporator Core Ice-Up	● Go to section 412-03, Pinpoint test D.
	● Intake Air Filter Contaminated	● Go to PinPoint Test I.
	● Mode (HIM)	● Go to PinPoint Test D, E, F, G, H, J.
	● Vehicle Carpet Wet	● Visual inspection to verify if the HVAC drain hose is blocked or misaligned with the hole in Transmission tunnel.
● Noise	● Blower Motor	● Go to section 412-04, Pinpoint test L.